

Mondi Štětí a.s.

STANDARD
ST 10.02.03
COUPLINGS

Mondi Štětí a.s.	STANDARD ST 10.02.03	Page: 1/3
-------------------------	-----------------------------	------------------

STANDARD

ST 10.02.03

COUPLINGS

Worked out by:
Name: Ing. S. Ryšan
Position: Head of servise
of paper machines

Verified by:
Name: Ing. H. Procházková
Position: IMS Coordinator

Approved by:
Name: Ing.Bc.Petr Bubla
Position: Head of
Maintenance Dpt.

Signed by: Ing. S. Ryšan
in her own hand

Signed by: Ing. H. Procházková,
in her own hand

Signed by: Ing.Bc.Petr Bubla,
in his own hand

Version: 01

Valid from: As of the date of issue

Printouts, if any, are not controlled.

Printed on: 28.09.2022

Mondi Štětí a.s.	STANDARD ST 10.02.03	Page: 2/3
------------------	----------------------	-----------

TABLE OF CONTENTS

	Page
1 Couplings of pumps, drives, compressors, blowers	3
2 General requirements	3
3 Coupling protection	3

Mondi Štětí a.s.	STANDARD ST 10.02.03	Page: 3/3
-------------------------	-----------------------------	------------------

1 Couplings of pumps, drives, compressors, blowers

Coupling types used:

- | | | |
|-----|---------------|--|
| 1.1 | Type: | ARPEX typ NEN
N-EUPEX - design type H with intersleeve |
| | Manufacturer: | FLENDER |
| 1.2 | Type: | SAMIFLEX |
| | Manufacturer: | Bomab
http://samiflex.se/EN/ |
| 1.3 | Type: | PINFLEX |
| | Manufacturer: | RENOLD |

If the coupling must be installed in the way that center boss are placed in intersleeve / form BAB / then it is necessary to use lamella packs in separated workmanship.

2 General requirements

If the coupling must be installed in the way that center boss are placed in intersleeve / form BAB / then it is necessary to use lamella packs in separated workmanship.

Connection will be carried out via feather according to ISO.

Boring tolerance of coupling complies with the tolerance of shaft end. The discrepancy from standard must be confirmed in individual cases before installation, alternatively before executive drawing approval.

3 Coupling protection

- Realization:
- realization from perforated plate for coupling checking by stroboscope
 - Stationary facture
 - Demountable by tools
 - fixing mainly on the foundation